

Standard Utility Notes

1. Contractor to only open up length of trench that can be constructed and backfilled in one working day in paved areas.
2. Contractor to place excavated materials in a dump truck and hauled to an approved location to wasted materials to paved areas.
3. Contractor to backfill trench with approved materials and stabilize disturbed areas the same working day.
4. In areas where the construction takes to place outside of the existing roadbed, Contractor to install silt fence along the downhill side of the trench before beginning construction and place excavated material from the trench on the uphill side.
5. If dewatering of the trench is required, Contractor to pump water to a filter bag to dewater.
6. Contractor to sweep streets of any debris or sediments caused by construction operations and dispose of at an approved location.
7. Contractor to stabilize all disturbed areas with seed & mulch or appropriate street repair.